7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

643

Number or quantity required.	Description	Number or quantity required.	Description
184 pipes ...	3" C. I. pipes 1,650 or 184 pipes at 1 cwt. per pipe.	600 R. ft. ...	¾" Galvanised pipe.
44 cwts. ...	2½" C. I. pipes 500' or 56 pipes at 88 lbs. per pipe.	6	1" Do bends.
8,600 R. ft. ...	1½" Galvanised pipe.	48	¾" Do elbows.
1	4"×2½" C. I. cross.	70 ...	1" Do do
1	4"×1½" do	5	¾" Do bends.
1	6"×3" C. I. branch.	9	1½"×1" Reducing collar.
2	3" plug.	3	1¼"×¾" Do do
7	3"×1½" C. I. branch.	30	1" Collar.
4	2½" C. I. collar.	16	¾" Do
2	2½" C. I. bend.	15	1" Chucknut.
2	2½"×1½" branches.	8	¾" Do
4	2½" W. I. plugs.	13	¾" Plugs.
5	1½" do	13 Waste ...	Waste not Bib cocks.
10	1½" Galvanised bends.	10	1" Gland cocks.
10	1½" do tee.	3	¾" Do
2	2½" Sluice valve.	10	1" Nipple.
17	1½" Gland cocks.	3	¾" Do
2,800 R. ft. ...	1" Galvanised pipe.	13	C. I. single tap fountains.
		30	Do road boxes.
		4	Do valve boxes.

S. SRINIVASA AIYAR,
Executive Engineer.

MYSORE DIVISION.

Notice.

The attention of the public is invited to the advertisement published in detail in the *Mysore Gazette*, dated 9th January 1919, calling for tenders for re-roofing with Mangalore Tiles the Second Class Travellers' Bungalow at Krishnarajpete and constructing a motor shed in the compound of the bungalow.

Notice.

The attention of the public is invited to the advertisement published in detail in the *Mysore Gazette*, dated 9th January 1919, calling for tenders for extending the Hindi Boys, School building at Gargeswari, T.-Narsipur Taluk, Mysore District.

A. PUTTUSAMAIA,
Executive Engineer.

KOLAR DIVISION.

Dated 8th January 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 12 noon of 10th February 1919, for constructing a Sub-Assistant Surgeon's and Midwife's quarters at Sidlaghatta. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1919.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing a Sub-Assistant Surgeon's and midwife's quarters at Sidlaghatta," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money of rejected tenders will be returned

Approximate estimate of quantities for constructing Sub-Assistant Surgeon's quarters at Sidlaghatta.

Sl. No.	Items	Unit	Quantity
1	Earthwork excavation and filling basement	C. yd.	70
2	Concrete in chunam	C ft.	1,155
3	Laterite stone in chunam	„	1,113
4	Burnt brick in mud	„	1,539
5	Burnt brick in chunam	„	493
6	Burnt stone slabs nicely dressed	S. ft.	282
7	Burnt stone slabs for pillars	„	48
8	Burnt stone square pillars at corners	L. S.	...
9	Honne wood work with wood oiling	C. ft.	59·05
10	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sq.	1,348
11	Mangalore ridge tiles set in mortar	R. ft.	62
12	Zinc sheet for valley	S. ft.	96
13	Teakwood eave board ornamental	R. ft.	169
14	Coping with brick in chunam and plastering over the compound wall and privy wall.	„	42
15	Teakwood panelled door complete with iron clamps, etc.	S. ft.	86
16	Teakwood windows with panelled shutters outside and glazed shutters inside with iron bars, etc.	„	61
17	Teakwood battened door with iron clamps	„	108
18	Teakwood windows with iron bars and shutters with iron clamps	„	42
19	Painting doors and windows with chocolate	Sq.	9·25
20	Flooring with 1st Class Mangalore tiles over 3" concrete and cement pointing	„	4·26
21	Flooring with Kadapa slabs over 3" concrete and cement pointing	„	2·30
22	Plastering with chunam	„	41·80
23	White and color washing	„	41·80
24	Constructing combined chimneys	L. S.	...
25	Constructing sets in latrine stone flooring, cement pointing, tarring to a height of 3' and drivage pits, etc.	L. S.	...
26	Gravelling the compound	L. S.	...
27	Pestle and mortar	L. S.	...
28	Pointing with chunam	Sq.	2·00
29	Chunam borders	S. ft.	70
30	Cup-boards with pegs to support	L. S.	...
31	Tarring wood work, etc.	L. S.	...

Approximate estimate of quantities for constructing Midwife's quarters at Sidlaghatta.

Sl. No.	Items	Unit	Quantity
1	Earthwork excavating and filling basement	C. yd.	44
2	Concrete filling	C. ft.	770
3	Laterite stone in chunam foundation and basement	„	687
4	Burnt brick in chunam	„	321
5	Do arch work	„	3
6	Burnt brick in mud superstructure	„	1,050
7	Burnt stone slabs nicely dressed	S. ft.	202
8	Honne wood work with wood oiling	C. ft.	48·00
9	Teakwood battened door with clamp	S. ft.	152
10	Teakwood windows with battened shutters with iron bars, etc., complete	„	41
11	Ventilators with expanded metal fixed in teakwood frames with iron clamps, etc.	„	25
12	Roofing with Mangalore tiles over teak reepers, complete	Sq.	8·50
13	Ridge tiles set in mortar	R. ft.	36
14	Teakwood ornamental eave board with pointing, etc., complete	„	170
15	Coping with burnt brick in lime with plastering, etc.	„	53
16	Cut stone pillars with base capital, etc., complete	No.	3
17	Flooring with Kadapa slabs also over 3" of concrete and cement pointing	Sq.	4·16
18	Plastering with chunam	„	31·19
19	White and colour washing	„	31·19
20	Pointing with chunam	„	1·21
21	Chocolate pointing	„	4·09
22	Constructing V-shaped drain to lead off drain	L. S.	...
23	Constructing seats in latrine stone flagging, tarring, etc.	L. S.	...
24	Tarring wood work on top of walls	L. S.	...
25	Pestle and mortar	L. S.	...
26	Constructing hearths and cistern	L. S.	...
27	Constructing a drain at junction of roof and chimney with cement plastering, etc.	L. S.	...
28	Cup-boards	L, S.	...

V. V. KARVE,
Executive Engineer.

MEDICAL DEPARTMENT.

MINTO OPHTHALMIC HOSPITAL, BANGALORE.

Abstract Notification.

Sealed tenders for the diet and other articles for the Minto Ophthalmic Hospital, for 6 months from the 1st of March to the 31st August 1919, both days inclusive will be received by the Superintendent on the 31st January 1919.

For details *vide Mysore Gazette* of 9th January 1919.

B. G. SRINIVASACHARYA,
Offg. Superintendent.